BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of work: Cleaning and Removal of silt at Open Drains at Kattigenahalli, Kogilu and Jakkur Surrounding areas in ward no. 05, Byatarayanapura sub division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	8331.05	KSRB 2-1.1: Earth work in surface excavation in **ordinary soil** for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications.	cum	159.84	
2	8331.05	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. **From 0.00 to 11.90 Km**	cum	62.20	

ಕರಡು ಟೆಂಡರ್ ಪಡ್ಯೂಲ್‌ನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....(Nil)
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

23.9.16

Chief Engineer
Yelahanka Zone
Bruhath Bangalore Mahanagara
Rangalore 92

Executive Engineer, 23/9
Byatarayanapura Division
BBMP, Bangalore - 92